

57
 Field Notes of the Survey of
 East boundary of Tp. 2 N.R. 32E.
 By James T. Currin and James E.
 Noland, under Special Contract
 Dated May 4th, 1887.

Chains		
	Beginning at cor. to Ts. 1 & 2, N. R. 32 & 33 E., I run North to re-established line bet. Tp. 2 N.Rs. 32 & 33 E. North on E. boundary Sec. 36, Var. 20° E.	
16.50	Ditch(dry) Course W.	-20
31.77	Dry Branch " "	
39.70	Found no trace of old corner. Set a basalt, stone 18x10x6 ins., 12 ins. in ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face. Dug pits 18 x 18 x 12 ins. N & S of corner 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.	
67.00	Summit of hill.	+100
79.40	Found pits and mound to old corner; set a basalt stone 9 x 8 x 7 in. 6 inches in ground for corner to secs. 25, 30, 31 & 36; marked 1 notch on S., 5 notches on N. edges; renewed pits, raised mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base along side. Land, rolling. Soil, 2nd rate. No grass.	
	North on E. boundary Sec. 25. Var. 20° East	
39.65	Found old mound and pits for $\frac{1}{4}$ Sec. corner. Set a basalt stone 9 x 8 x 7 in., 6 inches in ground for $\frac{1}{4}$ Sec. cor- ner, marked $\frac{1}{4}$ on W. face; re-dug pits, raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.	
70.00	Wagon road, course N.W.	
79.20	Found old pits and mound for Sec. corner. Set a basalt stone 18 x 6 x 6 in. 12 inches in ground for corner to secs. 19, 24, 25 & 30, marked 2 notches on South and 4 notches on North edges. Re-dug pits. Raised a mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base alongside. Land, rolling. Soil, 2nd rate. Scattering Sage Brush. Good Bunch Grass.	