

Re-established E. boundary T.2 N.R.32E.

| Chains | |
|--------|---|
| | <p>North on E. boundary Sec. 24.</p> |
| | <p style="text-align: right;">Var. 21° East</p> |
| 39.53. | <p>Found old mound and pits to $\frac{1}{4}$ Sec. corner. Set a basalt stone .9 x 8 x 7 ins., 6 inches in ground marked $\frac{1}{4}$ on W. face. Re-dug pits, raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.</p> |
| 79.00 | <p>Found old mound and pits to Sec. corner. Set a post 48 x 4 x 4 ins., 12 inches in ground for corner to Secs. 13, 18, 19 & 24, marked T. 2 N.S.18, on N.E. R. 33 E., S. 19, on S. E. R. 32 E. S. 24 On S.W. Sec. 13. On N.W. and found 3 notches on N & S edges. Re-dug pits, raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around corner.</p> <p>Land, rolling, sloping N & S. Soil, 1st rate. Bunch grass.</p> |
| | <hr/> |
| | <p>North on E. boundary of Sec. 13.</p> |
| | <p style="text-align: right;">Var. 20° 35' East</p> |
| 39.58 | <p>Found old pits and mound to $\frac{1}{4}$ Corner. Set a basalt stone 10 x 8 x 7 inches, 7 inches in the ground, marked $\frac{1}{4}$ on W. face; redug pits and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside. Enter Creek bottom.</p> |
| 48.40 | <p>Tudie Willow Creek, 4 links wide, course N.W.</p> |
| 52.00 | <p>Wagon Road, course N.W.</p> |
| 53.00 | <p>Leave creek bottom.</p> |
| 60.00 | <p>Summit of hill.</p> |
| 79.20 | <p>Found old pits and mound for Sec. corner. Set a basalt stone, 12 x 8 x 6 inches, 8 inches in the ground for corner to Secs. 7, 12, 13 & 18; marked 4 notches on S. and 2 on N. edges. Redug pits and raised earth mound 2 ft. high, $4\frac{1}{2}$ ft. base alongside.</p> <p>Land, rolling. Soil in creek bottom, alkali; rest, mixed, 2nd rate. Bunch grass, sage brush and alkali grass.</p> |