

Reestablished E. Bdry. T. 2 N.R. 32 E.

Chains		+80
	North on E. boundary Sec. 12. Var. 20° 21' East.	
3.50	Gulch, Course S.W.	
8.50	Pendleton & LaGrande wagon road, course S.E.	
10.00	Summit hill.	+80
40.00	Found no trace of old corner. Set a basalt stone 12 x 7 x 6 ins., 8 inches in ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face. Dug pits 18 x 18 x 12 inches N & S of corner 5 $\frac{1}{2}$ ft. distant and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.	-50
49.75	Wagon road, course E & W.	-20
50.15	O.S.L.R.R. Course E & W.	
51.00	Enter field and river bottom.	
60.76	Slough 50 links wide. Course E & W.	
71.00	Umatilla River, course W. 100 links wide.	
80.00	To old corner to Secs. 1, 6, 7 & 12. Set a post 48 x 4 x 4 inches for corner to Secs. 1, 6, 7 & 12, 24 inches in the ground, marked T. 2 N.R. 33 E., S. 6 on N.E., Sec. 7 on S.E., R. 32 E. S 12 on S.W., Sec. 1 on N.W. faces, 5 notches on South and 1 notch on N. edges, from which a balm tree, 12 in. diam. bears N. 65° W. dist., 13 links, marked T. 2 N.R. 32 E. S. 12 B.T. a balm tree, 12 in. diam. bears N. 55° W. dist., 15 links, marked S. 1, B.T. No other tree in limits. Land, hilly and bottom land. Soil on hills, 1st rate. In river bottom, gravelly, 3d rate. Balm timber & thick undergrowth in river bottom 29.85 chs.	
	North on E. boundary Sec. 1. Var. 20° East.	
3.00	Spring Branch, 10 links wide, course W. Leave river bottom.	
40.00	Set a basalt stone, 9 x 8 x 7 ins., 6 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face. Dug pits 18 x 18 x 12 ins. N & S of corner, 5 $\frac{1}{2}$ ft. distant; raised	