

## Reestablished E. Bdry. T. 2.N.R.32 E.

Chains  
 earth mound  $1\frac{1}{2}$  ft. high,  $3\frac{1}{2}$  ft. base alongside.

59.00 Dry gulch, course N.W.

61.00 Wagon road, course S.W.

62.05 Walla Walla Branch R.R. Course N.E. & S.W.

64.80 Dry bed Wild Horse Creek.

64.85 Intersect U.R. boundary on the bank of Wild Horse Creek and set a stone 12 x 10 x 8 ins. in diameter, marked U.R.M.C. on the S. face for meander corner to secs. 1 & 6. Dug a pit 3 ft. square, 1 ft. deep, 8 links North of stone and raised mound of earth 2 ft. high,  $4\frac{1}{2}$  ft. base over it.

80.60 To township corner to Tps. 2 & 3 North Ranges 32 & 33 E. Land, rough and hilly.  
 Soil, 2nd rate.  
 Timber and underbrush 3 chains.

---

The S.E. part of this township is rolling. The N & West hilly. Soil, 2nd rate except on McKay Creek, which is gravelly 4th rate. There is scattering cottonwood and thorn on McKay Creek. Poor grass on the rest.

---

Field Notes of Exam. of cors., Subdivisional Lines  
 In Tp. 2 N.R. 32 E., made by James P.  
 Currin and James E. Noland, under  
 Special Contract, dated May 4, 1887.

---

Going South between Secs. 14 & 15, passed the  $\frac{1}{4}$  Sec. corner, a stone 8 x 8 x 8 firmly set in the ground marked  $\frac{1}{4}$  on W. face, with pits N. & S.,  $5\frac{1}{2}$  ft. distant with mound of earth around it.

Found corner to sections 14, 15, 22 & 23, a stone about 10 x 8 x 7 firmly set in the ground with 2 notches on E. and 3 on S. edges. Pits in each section  $5\frac{1}{2}$  feet distant. Mound of earth leveled down so as to be around it. Pits in good repair.

---