

4

Subdivisions, T. 2 N.R. 32 E.

Chains	
	30, 31, 25 & 36. Thence N. 89° 39' W. on true line.
40.00	Found old $\frac{1}{4}$ Sec. corner. Reset stone 16 x 8 x 4 ins., 10 inches in the ground for $\frac{1}{4}$ Sec. corner. Marked $\frac{1}{4}$ on N. face and redug pits 18 x 18 x 12 ins. E. & W. from stone, $5\frac{1}{2}$ ft. distant, and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
80.00	To corner to Secs. 25, 26, 35 & 36. Land, rolling. Soil, 1st rate. No timber. Poor bunch grass.
	North on random between Secs. 25 & 26, retracing old line.
40.00	Set temp. $\frac{1}{4}$ Sec. corner. Var. 21° East.
79.60	Intersect line 15 links W. of Old Corner to Secs. 23, 24, 25 & 26. Reestablished corner by setting a stone 9 x 8 x 7 ins., 6 inches in the ground, marked with 2 notches on S. and 1 on E. edges. Dug pits 18 x 18 x 12 ins., in each section, $5\frac{1}{2}$ ft. distant and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside. Thence S. 06' W. on true line. Va. 21° East.
39.80	Set stone 7 x 8 x 9 ins., 6 inches in the ground for $\frac{1}{4}$ Sec. corner; marked $\frac{1}{4}$ on West face; dug pits 18 x 18 x 12 inches N & S from stone, $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.
79.60	To corner to Secs. 25, 26, 35 & 36. Land, rolling. Soil, 1st rate. No timber. Poor bunch grass.