

## Subdivisions, T. 2 N.R. 32 E.

|        |  |      |
|--------|--|------|
| Chains |  |      |
| 40.00  | To corner to Secs. 1, 2, 11 & 12.<br>Good bottom land; North of river, rough and rocky.<br>Scattering Cottonwood and underbrush.   |      |
|        | From the corner to Secs. 2, 3, 34 and 35 on the South boundary of Tp., I run<br>North on random between Secs. 34 & 35.<br>Va. 21° East.  |      |
| 40.00  | Set temporary $\frac{1}{4}$ Sec. corner.   |      |
| 80.00  | To a point 35 links East of old corner to Secs. 26, 27, 34 & 35, which I reestablished. Set stone 15 x 10 x 7 ins., 10 inches in the ground, marked with 2 notches on E. and 1 on S. edges. Redug pits 18 x 18 x 12 ins., in each section, $5\frac{1}{2}$ ft. distant and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside; thence S. 15' East on true line.<br>Va. 21° 30' East. |      |
| 10.10  | Gulch, course N.E.   | -10  |
| 20.00  | Summit of ridge.   | +30  |
| 40.00  | To old $\frac{1}{4}$ Sec. corner. Reset stone 10 x 8 x 6 ins., 6 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N. & S. from stone $5\frac{1}{2}$ ft. distant. Raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft base over it.   |      |
| 47.00  | Summit of ridge.   | +100 |
| 80.00  | To corner to Secs. 2, 3, 34 & 35.<br>Land, rolling.<br>Soil, 1st rate.<br>No timber. Bunch grass.  |      |
|        | East on random between Secs. 26 & 35.<br>Va. 21° 30' East.   |      |
| 40.00  | Set temp. $\frac{1}{4}$ Sec. corner.   |      |
| 80.25  | Intersect East boundary 40 links N. of corner to Secs.   |      |