

Subdivisions, T. 2 N.R. 32 E.

Chains	
	<p>in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on West face. Redug pits 18 x 18 x 12 ins., N & S. from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.</p>
80.00	<p>To corner to Secs. 26, 27, 34 & 35. Land, rolling. Soil, good. No timber. Bunch grass.</p>
<hr/>	
	<p>East on random between Secs. 23 and 26. Va. 20° East.</p>
40.00	Set temporary $\frac{1}{4}$ Section corner.
79.80	Intersect East boundary 30 links N. of corner to Secs. 23, 24, 25 & 26; thence North 89° 47' W. on true line.
39.90	<p>Found old $\frac{1}{4}$ Sec. corner. Set stone 7 x 8 x 9 ins., 6 inches in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on N. face. Redug pits 18 x 18 x 12 ins. E & W. from stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
41.00	Dry gulch. Course S.
75.75	Road bears N & S.W.
79.80	<p>To corner to Secs. 22, 23, 26 & 27. Land, rolling. Soil, good. No timber. Some grass.</p>
<hr/>	
	<p>North on random between Secs. 22 and 23. Var. 20° East.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.80	<p>Intersect N. boundary at old corner to Secs. 14, 15, 22 & 23. Found old mound and pits; restored corner by setting a basalt stone 12 x 7 x 6 ins., 8 inches in the ground, marked with 3 notches on the South and 2 notches on the East edges; redug pits and raised a mound of earth 2 ft. high and $4\frac{1}{2}$ ft. base around it. Thence,</p>