

Subdivisions, T. 2 N. R. 32 E.

Chains	
80.00	<p>12 ins. E. and W. from stone <math>5\frac{1}{2}</math> ft. dist., and raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base alongside.</p> <p>To corner to Secs. 10, 11, 14 and 15.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>No timber. Poor grass.</p>
23.86	<p>North on true line bet. Secs. 10 &amp; 11.</p> <p style="text-align: right;">Var. <math>21^{\circ}</math> East.</p> <p>Descend gradually.</p> <p>Intersect South bdy. line of the "Reserve" Addition to the Town of Pendleton. Set stone 10 x 10 x 12 ins., 8 inches in the ground for closing corner to fractional sections 10 &amp; 11, marked U.R.C.C. on S. face. Dug pits S.E. and W. 18 x 18 x 12 ins. <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth 2 ft. high, <math>4\frac{1}{2}</math> ft. base alongside.</p> <p>Land, 1st rate, rolling.</p> <p>No timber, poor grass.</p> <p style="text-align: right;">July 28th, 1887.</p>
40.00	<p>From the corner to Secs. 3, 4, 33 &amp; 34, S. bdy. of Tp..</p> <p>I run</p> <p>North on random bet. Secs. 33 &amp; 34.</p> <p style="text-align: right;">Var. <math>19^{\circ}</math> East.</p> <p>Set temporary <math>\frac{1}{4}</math> Sec. corner.</p>
80.00	<p>Old corner, reset stone 10 x 9 x 8 ins., 7 inches in the ground for corner to Secs. 27, 28, 33 &amp; 34. Dug pits 18 x 18 x 12 inches in each section <math>5\frac{1}{2}</math> ft. dist., and raised a mound of earth 2 ft. high, <math>4\frac{1}{2}</math> ft. base alongside; thence</p> <p>S. on true line.</p> <p style="text-align: right;">Var. <math>20^{\circ}</math> East.</p>
16.35	<p>McKay Creek, 30 links wide, course N.W.</p>
22.00	<p>Creek bottom, Course N.W. &amp; S.E.</p>
40.00	<p>Old <math>\frac{1}{4}</math> Sec. cor. Reset stone 10 x 8 x 8 ins., 7 ins. in the ground for <math>\frac{1}{4}</math> Sec. corner, marked <math>\frac{1}{4}</math> on W. face, re-</p>