

Subdivisions, T. 2 N. R. 32 E.

Chains	
79.50	Intersect N. bdy. 54 lks. W. of Old Cor. to secs. 9, 10, 15 & 16, which I restored by setting stone 9 x 8 x 8 ins. 6 ins. in the ground, marked with 4 notches on S. and 3 on E. edges. Redug pits 18 x 18 x 12 ins. in each sec. 5½ ft. dist. and raised a mound of earth 2 ft. high, 4½ ft. base over it. Thence, S. 23° W. on true line.
39.75	Set a basalt stone 10 x 9 x 8 ins., 7 ins. in the ground for ¼ Sec. corner, marked ¼ on W. face, dug pits 18 x 18 x 12 ins. N & S. of cor. 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base alongside.
79.50	To cor. to Secs. 15, 16, 21 & 22. Land, rolling. Soil, good. No timber.
East on random bet. Secs. 10 & 15. Var. 20° East.	
40.00	Set temp. ¼ Sec. cor.
79.46	Intersect E. bdy. 16 lks. S. of cor. to Secs. 10, 11, 14 & 15. Thence, S. 89° 53' W. on true line. Var. 21° E.
35.00	Descend.
39.73	Set a stone 16 x 12 x 10 ins., 11 ins. in the ground for ¼ Sec. cor. marked ¼ on N. face. Raised a mound of stone alongside. Pits impracticable.
47.25	Trudie Willow Creek, 5 links wide, Course N.W.
48.50	House 1 ch. N.
56.00	Intersect bdy. line of Reserve Addition to Pendleton. Set a basalt stone 12 x 8 x 7 ins., 8 ins. in the ground for U. R. closing cor., marked U.R.C.C. on E. face. Dug pits 18 x 18 x 12 ins. S.W., N.E. & E. of stone 5½ ft. dist., raised earth mound 2 ft. high, 4½ ft. base alongside.
70.85	Intersect Reserve Bdy. of Pendleton. Set a stone 9 x 8 x