

Subdivisions, T. 2 N.R. 32 E.

Chains	
70.00	Leave creek bottom, course N.W. S.E.
80.00	To corner to Secs. 16, 17, 20 & 21.
	Land, mostly in level bottom.
	Soil, good.
	Thorn and willow.
<hr/>	
	East on random bet. Secs. 9 & 16.
	Var. 21° 30' East.
40.00	Set temp. $\frac{1}{4}$ Sec. corner.
80.00	Intersect N & S line 24 lks. N. of Cor. to Secs. 9, 10, 15 and 16. Thence,
	N. 89° 50' W. on true line.
	Var. 20° East.
5.00	Wagon Road, Course N.E.
20.00	" " and top of hill.
40.00	Set stone 7 x 8 x 12 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on N. face. Dug pits 18 x 18 x 12 ins. E. and W. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.
66.00	Enter Creek bottom, course N. & S.
71.00	Irrigation ditch, dry, 5 lks. wide, N & S.
80.00	To cor. to Secs. 8, 9, 16 & 17.
	Land, gently rolling.
	Soil, 2nd rate.
	No grass.
<hr/>	
	West on random bet. secs. 8 & 17.
	Var. 21° 30' East.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect N & S line 14 links S. of Cor. to Secs. 7, 8, 17 & 18. Thence,
	S. 89° 54' E. on true line.
	Var. 21° East.
	Ascend.
38.00	Intersect U. R. boundary and set a stone 12 x 10 x 9 ins.