

Subdivisions, T. 2 N. R. 32 E.

Chains

General Description

This township is mostly rolling land. The land along McKay Creek is gravelly. The rolling land has no timber and very little grass. On the Tudie Willow, the soil is alkaline, covered with wire and swamp grass in places; sage brush in others. Timber, Cottonwood, Thorn, Willow and Choke Cherries.
 July 29th, 1887.

Resurvey of Subdivisions, T.2,N.R.32E.,
 By James P. Currin and James E. Noland,
 Under Special Contract, dated May 4, 1887.

From Sec. corner Secs. 23,24,25 & 26, which is a md. with pits in each sec. $5\frac{1}{2}$ ft. dist. The stone has been taken out and is gone. The old original post lies near by but marks on it are illegible. Md. and pits are conspicuous but are partially destroyed.

Had no material to make a new corner.

I ran N.10°E. bet. Secs. 23 & 24.

Var. 21° East

40.10 Found $\frac{1}{4}$ Sec. corner a stone 18 x 12 x 6 ins., firmly set in the ground, marked $\frac{1}{4}$ on W. face, with pits N & S, $5\frac{1}{2}$ ft. dist., partly filled; md. about the stone almost gone.

42.20 Dry bed of gulch, course W.

-20 ft.

80.20 To cor. to Secs. 13, 14, 23 & 24, a stone 18 x 12 x 10 ins., firmly set in the ground, marked with 1 notch on E. and 3 on S. edges. Mound partly gone. Pits in each Sec. $5\frac{1}{2}$ ft. dist. in good condition.

The original pencilling shows the reported dist. to be erroneous.

Land, rolling. Soil, 2nd rate. Some grass.

From cor. sec. 11, 12, 13 & 14, which is a stone 15x8x4 ins. firmly set in the ground with 1 notch on E. & 4 on S. edges. Pits in each sec. $5\frac{1}{2}$ ft. dist. Md. mostly