

Resurvey Subdivisions T. 2. N. R. 32 E.

Chains

	gone. I run North between secs. 11 & 12. Var. $20\frac{1}{2}^{\circ}$ East	
5.15	Gulch, course W.	-50
15.00	Top of hill, course E & W.	
29.00	Road " E & W.	
40.00	To $\frac{1}{4}$ Sec. cor., which is a stone 9x8x7 ins., 6 ins. in ground, with pits N & S, $5\frac{1}{2}$ ft. dist. Stone was marked $\frac{1}{4}$ on W. face, all in good condition. Earth md. mostly gone.	
57.90	Intersect line to Reservation of Pendleton, find a stone 12 x 10 x 10 firmly set in the ground marked C C U R on S. face with pits E.S. & W. of it, $5\frac{1}{2}$ ft. dist., well pre- served. E. md. mostly gone. The error in distance on this line also between 10 & 11 was made in copying original notes.	
	From cor. secs. 10, 11, 14 & 15, which is a stone 15x8x9 ins. with 2 notches on E. & 4 on S. edges. Md. scatter- ed. Pits in each sec., $5\frac{1}{2}$ ft. dist., partly filled. Re- set the stone in md. as I found it pulled out. Thence North between secs. 10 & 11. Var. 21° East.	
	Descend gradually.	
22.75	Intersect S. line of Reserve Addition to Pendleton. Find the ground plowed up and corner gone. Set a stone 14 x 9 x 6 ins., 9 ins. in ground, marked C C U R on S. face. Dug pits 18 x 18 x 12 ins., E.S. & W. $5\frac{1}{2}$ ft. distant, raised md. of earth, $1\frac{1}{2}$ ft. high by $3\frac{1}{2}$ ft. base along- side. Thence I measured N. $66^{\circ} 24'$ E.	
6.45	To monument No. 3.	
	From cor. secs. 9, 10, 15 & 16, which is a stone 9 x 8 x 8 ins. firmly set in the ground with a pit $5\frac{1}{2}$ ft. dist. in each sec. stone is marked with 3 notches on E., and 4	