

## Resurvey of Subdivisions T.2,N.R. 32 E.

## Chains

ins., marked C C U R on S. face. Set it 8 ins. in ground and raised md. of stone alongside and dug a pit 18 x 18 x 12, 5½ ft. S. W. of it, throwing the dist. on the rock md. This cor. is near bank of creek.

From cor. secs. 10, 11, 14 & 15, which is a stone 12x10x8 ins. firmly set in the ground with 2 notches on E. and one on S. edges, with a pit 5½ ft. dist., in each sec. in good condition. Md. of earth is mostly blown away. I ran S. 89° E. on a random line between secs. 11 & 14.

Var. 21° E.

40.25 1/4 sec. corner in good condition.

80.50 E. bdy. at N. cor. to secs. 11, 12, 13 & 14.

N. 89° W. on true line.

Var. 21½° East.

10.00 Dry ditch, course N.

32.00 Summit of ridge.

40.25 To the ¼ cor. a stone 9 x 8 x 7 ins. firmly set in the ground, marked ¼ on N. face, pits E & W. 5½ ft. dist. in good condition. Md. of earth settled down.

80.50 To sec. cor.

Land, rolling.

Soil, 2nd rate.

April 29th, 1890.

±100