

Field Notes of the Survey of the  
 North boundary of T. 1 N.R. 33 E., by  
 David P. Thompson, under his Contract  
 No. 106, dated August 16th, 1864.  
 (S. bdy. T. 2 N.R. 33 E.)

Chains	
	East on North boundary of Sec. 6. <p style="text-align: right;">Variation 20° East.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.
62.93	Road bears N & S.
80.00	Set post for corner to secs. 5, 6, 31 & 32 in mound of earth with charred stake, pits, trench &c., as per instructions.  Land, level. Soil, 1st rate.
	East on North boundary of Sec. 5. <p style="text-align: right;">Variation 19°30' East.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.
80.00	Set post for corner to secs. 4, 5, 32 & 33 in mound of earth with charred stake, pits, trench &c., as per instructions.  Land, level. Soil, 1st rate.
	East on North boundary of Sec. 4. <p style="text-align: right;">Variation 19° 30' East</p>
40.00	Set $\frac{1}{4}$ Sec. post in mound of earth with charred stake, pits, trench &c., as per instructions.
80.00	Set post for corner to secs. 3, 4, 33 & 34 in mound of earth with charred stake, pits, trench &c., as per instructions.  Land, level. Soil, 1st rate.
	East on North boundary of Sec. 3. <p style="text-align: right;">Variation 19°30' East.</p>
40.00	Set stone 17 x 8 x 6 in. for $\frac{1}{4}$ Sec. corner.
40.10	Dry bed of creek; course N.W.