

E. bdry. T. 2 N.R. 33 E.

Chains	
	<p>North on East boundary of Sec. 12.</p> <p style="text-align: right;">Variation 21° East.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.
48.00	Enter timber, bears E & W.
66.00	Umatilla River, 50 links wide, runs West.
68.00	Leave Timber, bears E & W.
80.00	Set stone 24 x 12 x 4 in. for corner to secs. 6, 7, 1 & 12.
	<p>Land, gently rolling.</p> <p>Soil, 1st rate.</p> <p>Timber: Cottonwood, birch and willow.</p>
<hr/>	
	<p>North on East boundary of Sec. 1.</p> <p style="text-align: right;">Variation 20° East.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.
80.00	Set post for corner to Townships 2 & 3, North Ranges 33 & 34 East in mound of earth with charred stake, pits, trench &c., as per instructions.
	<p>Land, level.</p> <p>Soil, 2nd rate.</p>
	September 18th, 1864.
<hr/>	
	N. Boundary T. 2 N.R. 33 E.
<hr/>	
	<p>I then run West between Townships 2 and 3 North Range 33, East and set temporary half mile and mile posts at 40.00 and 80.00 chains.</p> <p>I find the line to be 5 miles, 79 chains and 62 links and the falling to be 36 links North of Township corner. The correction will, therefore, be 6 links South per mile.</p> <p>From the corner to Townships 2 & 3 North Range 32 & 33 East, I run</p>