

N. Boundary, T. 2 N. R. 33 E.

Chains

N. 89° 58' East on North boundary of Sec. 6.
 Var. 16°15' East.

Descend.

- 33.00 Dry bed of creek, course N.W., foot of hill.
- 39.62 Set post for $\frac{1}{2}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.
- 79.62 Set post for corner to Secs. 5, 6, 31 & 32 in mound of earth with charred stake, pits, trench &c., as per instructions.

-200

Land, gently rolling.
 Soil, 1st rate.

Sept. 20th, 1864.

N. 89° 58' East on North boundary of Sec. 5.
 Var. 19°30' East

- 40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.
- 80.00 Set post for corner to secs. 4, 5, 32 & 33 in mound of earth with charred stake, pits, trench &c., as per instructions.

Land, level.
 Soil, 1st rate.

N. 89° 58' E. on North boundary of Sec. 4.
 Var. 20° 30' East.

- 40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.
- 80.00 Set post for corner to secs. 3, 4, 33 & 34 in mound of earth, with charred stake, pits, trench &c., as per instructions.

Land, level.
 Soil, 1st rate.

N. 89° 58' E. on North boundary of Sec. 3.
 Var. 20°30' East.