

Field Notes of the Survey of
Exterior Boundaries of T. 2,
N. R. 33 E. W. M., made by
Z. F. Moody, under Contract
Dated April 23, 1871.

Chains	North on East boundary of Sec. 36. Var. 21° East.
40.00	Set stone 14 x 12 x 10 for $\frac{1}{4}$ Sec. corner.
80.00	Set stone 18 x 16 x 14 for corner to Secs. 25, 36, 30 & 31. Land, stony. Soil, 2nd rate. Some grass.
	North on East boundary of Sec. 25. Var. 21° 30' East.
40.00	Set stone 14 x 14 x 12 for $\frac{1}{4}$ Sec. cor.
80.00	Set post and made stone mound for corner to Secs. 24, 25, 19 and 30. Land, sloping North. Soil, 1st rate. Good grass.
	North on East boundary of Sec. 24. Var. 21° East.
15.10	Brook, 8 lks., flows N. E.
40.00	Set post and earth mound for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for cor. to secs. 13, 24, 18, 19. Land, level. Soil, 1st rate. Good grass.
	North on East boundary of Sec. 13. Var. 21° East.
16.24	LaGrande and Pendleton road, course E & W.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for corner to Secs. 7, 12, 13 & 18. Land, level. Soil, 1st rate. Good grass.
	North on East boundary of Sec. 12. Var. 21° East.

-75