

E. Boundary T. 2 N. R. 33 E.

Chains	
8.00	Wagon road, course E & W.
23.50	Umatilla River, course W.
40.00	Set stone 16 x 14 x 8 for $\frac{1}{4}$ S. cor.
80.00	Set post and made mound of earth for corner to secs.
	1, 12, 6 & 7.
	Land, level.
	Soil, 1st rate.
<hr/> North on East boundary of Sec. 1.	
	Var. 21° East.
40.00	Set post and made stone mound for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for cor. to Tps. 2 & 3
	North Ranges 33 & 34, East.
	Land, rolling.
	Soil, 1st rate. Good grass.
	May 19, 1871.
<hr/> N. Boundary T.2 N.R. 33 E.	
<hr/> West on a random line on the North boundaries of Sections	
	1, 2, 3, 4, 5, 6.
	Var. 21° 30' East.
	I set temporary half mile and mile posts at every 40 and
	80 chains and at 6 miles and 5 links to a point 2 chs.
	and 84 links North of the South cor. to Township 3 North
	Range 32 East. Thence
	N. 89° 40' East on true line on North boundary of Sec. 6.
	Var. 18° 30' East.
31.80	Wagon road N.E. & S.W.
33.30	Wild Horse Creek, course S W, 10 lks. wide.
40.84	Set post and made earth mound for $\frac{1}{4}$ Sec. corner.
80.84	Set post and made earth mound for corner to Secs. 5, 6,
	31, 32.
	Land, rolling.
	Soil, 1st rate.