

Subdivisions, T. 2 N. R. 33 E.

Chains	
	N. 89° 50' W. on true line.
39.95	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
47.00	Agency buildings bear N. 15° W.
79.90	To corner. The Agency buildings bear N. 45° E. Land, rolling. Soil, sandy.
<hr/>	
	North between Secs. 9 & 10.
15.00	Wagon road, course E & W.
32.50	Enter field.
35.50	Spring Branch 10 lks., flows N.W.
40.00	A Balm tree, 15 ins. diam. for $\frac{1}{4}$ Sec. corner.
60.00	Leave field and enter timber.
75.00	Umatilla river, 2 chs., flows N.W.
80.00	Set post and made stone mound for corner to Secs. 9, 10, 3 & 4. Land, generally level. Soil, 1st rate in field.
<hr/>	
	East on random between Secs. 3 & 10. Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.25	Intersected N & S line 21, S. of corner. S. 89° 51' W. on true line.
40.12	Set post on bank of river for $\frac{1}{4}$ Sec. corner. A Balm 10 ins. dia. bears N 45° E. 25 lks.
80.25	To corner. Land subject to inundations.
<hr/>	
	North on random between Secs. 3 & 4.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.18	Intersected North boundary 24 lks. W. of corner. S. 00° 10' W. on true line.
40.18	Set post and stone mound for $\frac{1}{4}$ S. corner.
60.00	House, bears W. about 2 chains.