

Subdivisions, T. 2 N.R. 33 E.

Chains	
39.90	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
79.90	To corner.
	Land, level.
	Soil, 1st rate.
North between Secs. 7 & 8.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
59.00	Enter field in river bottom.
75.00	Leave field.
80.00	Set post for corner to Secs. 7, 8, 5 & 6, and made stone mound.
	Land, level.
	Soil, 1st rate.
East on random between Sections 5 & 8.	
	Var. 20° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersected N & S line 12 links S. of corner.
	S. 89° 55' W. on true line.
40.05	Set stone 17 x 14 x 10 for $\frac{1}{4}$ Sec. corner.
42.30	Umatilla river 2 chains wide flows N.W.
80.10	To corner.
	Land, level.
	Soil, 2nd rate.
West on random between Secs. 6 & 7.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.54	Intersected N & S line at corner.
	East on true line.
30.00	Umatilla river, 2 chs. wide, flows S.W..
39.54	Set stone 14 x 14 x 9 for $\frac{1}{4}$ Sec. corner.
79.54	To corner.
	Land, level.
	Soil, gravelly.