

Allotments, T. 2 N., R. 33 E.

Chains	
40.05	Set temporary $\frac{1}{4}$ S. cor.
60.00	Set post for $\frac{1}{16}$ S. cor.
62.00	Enter Indian field.
80.10	To the $\frac{1}{4}$ S. corner on S. bdy. of Section.
	Thence
	N. $89^{\circ} 38'$ West on N. bdy. of Sec. 12.
50.00	Set post and made mound of earth for $\frac{1}{32}$ Sec. corner.
60.00	Set stone 14 x 9 x 8 for $\frac{1}{16}$ Sec. corner.
61.44	Leave Indian field.
70.00	Set stone 17 x 12 x 9 for $\frac{1}{32}$ Sec. corner.
79.82	To sec. corner.
	The land in this Section, 12, is level. The soil is good 2nd rate. Some parts are good for garden and grain fields.
	A good growth of timber on river.
	North on West bdy. of Sec. 1.
20.00	Set stone 12 x 10 x 7 for $\frac{1}{16}$ Sec. corner.
	Thence
	East on random from $\frac{1}{16}$ Section corner to the $\frac{1}{16}$ Sec. corner on E. bdy. of Section 1.
79.90	Intersected E. bdy. of Sec. at $\frac{1}{16}$ Sec. corner.
	W. on true line.
10.00	Set stone 12 x 11 x 6 for $\frac{1}{32}$ S. corner.
20.00	Set stone 18 x 12 x 9 for $\frac{1}{16}$ Sec. corner.
30.00	Set post for $\frac{1}{32}$ Sec. corner.
39.95	To $\frac{1}{16}$ Sec. corner.
50.00	Set stone 14 x 12 x 7 for $\frac{1}{32}$ S. corner.
60.00	Set post for $\frac{1}{16}$ S. corner.
70.00	Set post for $\frac{1}{32}$ S. corner.
79.90	To $\frac{1}{16}$ Sec. cor. on W. bdy. of Section.
	Thence
	North on W. bdy. of Sec. 1.
40.20	To $\frac{1}{4}$ Section corner.
	Thence
	East on random from $\frac{1}{4}$ S. corner on W. bdy. to $\frac{1}{4}$ Sec. cor. on E. bdy. of Sec. 1.