

Allotments, T. 2 N.R. 33 E.

Chains	
	Thence
	East on random from 1/16 Sec. corner in S.W. Qr. to 1/16 S. cor. in S.E. Qr. of Sec. 10.
79.92	Intersected E. boundary of Sec. at corner. W. on true line.
10.00	Set post for 1/32 S. corner.
20.00	Set post for 1/16 S. corner.
30.90	Set post for 1/32 S. corner.
39.96	To 1/16 S. corner.
50.00	Set post for 1/32 S. corner.
60.00	Set post in mound of earth for 1/16 Section corner.
70.00	Set post for 1/32 S. corner.
79.92	To 1/16 Sec. corner.
	Thence
	North on West bdy. of Sec. 10.
32.50	Enter Indian field.
40.00	To a Balm tree for 1/4 Sec. corner
	Thence
	East on random from $\frac{1}{4}$ Sec. corner on W. bdy. to $\frac{1}{4}$ S. cor. on E. bdy. of Section 10.
80.00	Intersected E. bdy. at $\frac{1}{4}$ Sec. corner. West on true line.
10.00	Set post in stone mound for 1/32 S. corner.
15.00	Enter field.
20.00	Set post in mound of stone for 1/16 Sec. corner.
30.00	Set post in stone mound for 1/32 S. corner.
40.00	Set post in mound of stone for $\frac{1}{4}$ Section corner.
50.00	Set post in mound of stone for 1/32 S. corner.
60.00	Set post in mound of stone for 1/16 S. corner.
70.00	Set post in mound of stone for 1/32 S. corner.
80.00	To $\frac{1}{4}$ Section corner.
	Thence
	North on West boundary of Section 10.
60.00	Set post in stone mound for 1/16 S. corner.
	Thence