

## Allotments, T. 2 N. R. 33 E.

Chains	
	Thence
	W. on N. boundary of Sec. 10.
50.00	Set post in mound of stone for 1/32 Sec. corner.
60.00	Set post in stone mound for 1/16 S. corner.
70.00	Set post in mound of stone for 1/32 S. corner.
80.24	To Section corner.
	The land in Section 10 is generally good. A large field on South side of river is in a good state of cultivation.
	North on West boundary of Sec. 3.
20.00	House West 2 chains.
20.00	Set post for 1/16 Sec. corner.
	Thence
	East on random from 1/16 Sec. corner, to 1/16 Sec. cor. on E. boundary of Sec. 3.
80.16	Intersected E. boundary at 1/16 Sec. corner.
	West on true line.
10.00	Set stone 16 x 15 x 5 for 1/32 S. corner.
20.00	Set post in earth mound for 1/16 S. corner.
30.00	Set stone 14 x 10 x 6 for 1/32 S. corner.
40.08	To 1/16 Sec. corner.
50.00	Set post in stone mound for 1/32 Section corner.
60.00	Set post in stone mound for 1/16 S. corner.
70.00	Set post in mound of stone for 1/32 S. corner.
80.16	To 1/16 Sec. corner in S.W. Qr. of Section 3.
	Thence
	North on West boundary of Section 3.
40.00	Set post for $\frac{1}{4}$ Sec. corner.
	Thence
	East on random from $\frac{1}{4}$ Sec. corner in W. boundary of Sec. 3 to $\frac{1}{4}$ S. corner in E. boundary of Sec. 3.
80.10	Intersected East boundary of Sec. 3, 14 links N. of $\frac{1}{4}$ Sec. corner.
	N. 89° 54' W. on true line.