

Allotments, T. 2 N., R. 33 E.

Chains	
	<p>of stone around it.</p> <p style="text-align: center;">Thence</p> <p>I run East on true line between Secs. 6 & 7.</p> <p style="text-align: right;">Variation 20° East.</p>
16.50	<p>Set post 3 ft. long, 3 ins. square with marked stone 12 ins. in the ground for 1/32 Sec. corner marked 1/32 S. on N. face, dug pit 18x18x12 ins. E & W of post, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
36.50	<p>Intersected the ¼ Sec. corner between Secs. 6 & 7, which is a balm 4 ins. diam., marked 1/4 S. on N. face, from which</p> <p style="padding-left: 40px;">A balm 4 ins. diam., bears N.40° E. 40 lks. dist., marked 1/4 S.B.T.</p> <p style="padding-left: 40px;">A balm 8 ins. diam., bears S. 10° W. 58 lks. dist., marked 1/4 S.B.T.</p> <p>Land, brushy.</p> <p>Soil, 1st rate. Gravelly.</p>
	<hr/> <p>From the closing corner to Secs. 6 & 7 on West boundary of Township, I run</p> <p>North between Secs. 1 & 6 on a true line.</p> <p style="text-align: right;">Variation 19°30' East.</p>
10.00	<p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face; dug pits 18 x 18 x 12 ins., N & S of stone 5½ ft. distant and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
	<hr/> <p>From 1/16 Sec. corner, 20 chs. W. of ¼ Sec. corner, between Secs. 6 & 7</p> <p style="text-align: center;">I run</p> <p>North on true line in Sec. 6.</p> <p style="text-align: right;">Variation 19° 30' East.</p>
10.00	<p>Set stone 10 x 8 x 6 ins., 6 ins. in the ground for 1/32</p>