

Allotments, T. 2 N., R. 33 East

Chains 60.00	<p>Set basalt stone 11 x 8 x 7 ins., 7 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face, and raised a mound of stone alongside. Pits impracticable.</p> <p>Land, rolling and barren.</p> <p>Soil, ashy.</p>
	<p>From the 1/16 Sec. corner, 20 chains S. and 60 chains W. of $\frac{1}{4}$ Sec. corner, between Secs. 5 & 6, I run North on random line in Sec. 6.</p> <p style="text-align: right;">Var. 20° East.</p>
20.00	<p>Intersect 11 links East of 1/16 Sec. corner, 60 chains West of $\frac{1}{4}$ Sec. corner between Secs. 5 & 6.</p> <p style="text-align: center;">Thence, I run</p> <p>South 19' East on true line in Sec. 6.</p> <p style="text-align: right;">Variation 20° East.</p>
2.25	Gulch, course N.W.
9.50	Road " N.W.
18.50	Summit " "
20.00	<p>To the 1/16 Sec. corner 60 chains W. and 20 chs. S. of $\frac{1}{4}$ Sec. corner between Secs. 5 and 6.</p> <p>Land, rolling and barren..</p> <p>Soil, ashy and barren.</p>
	Section 8.
	<p>From the $\frac{1}{4}$ Sec. corner between Secs. 8 & 9, which is a charred stake and pits 18 x 18 x 12 ins. N & S of stake, 5$\frac{1}{2}$ ft. distant, mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it. In N. pit a stake 2 ins. square, marked 1/4 S. on W. face, I run</p> <p>North on true line between Secs. 8 & 9.</p> <p style="text-align: right;">Var. 20° 15' East,</p>
5.00	Road, course E & W.
7.50	Dry ditch, course W.
10.00	<p>Set stone 10 x 9 x 5 ins., 6 ins. in the ground for 1/16 and 1/32 Sec. corner marked 1/16 on N and 1/32 on W.</p>