

Allotments, T. 2 N. R. 33 E.

Chains	
5.00	<p>From 1/16 Sec. cor., 20 chs. W. of $\frac{1}{4}$ Sec. between Secs. 9 & 10, which is a basalt stone 12 x 8 x 8 ins., 8 ins. in the ground, marked 1/16 on N face and mound of stone and earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, I run North on true line in Section 9.</p> <p style="text-align: right;">Variation 21° East.</p>
17.60	Spring branch, 4 links wide, course N.W.
20.00	<p>Railroad, course N. 85° W.</p> <p>Set post 3 ft. long, 3 ins. square, with marked stone 12 ins. in the ground for 1/16 and 1/32 section corner, marked 1/16 S on S.E. face and 1/32 S on N.E. face; dug pits 18x18x12 ins. N & S of post, $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p style="text-align: right;">Variation 20°30' East</p>
29.80	Fence, course E & W.
30.00	<p>Set basalt stone 10x8x7 ins., 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W face and raised a mound of stone over it. Pits impracticable. Thence, I run S. 89° 54' E. on random line in Sec. 9.</p> <p style="text-align: right;">Variation 20° East.</p>
19.96	<p>Intersect 10 lks. N of 1/32 Sec. cor. between Secs. 9 & 10.</p> <p style="text-align: center;">Thence, I run</p> <p>N. 89° 37' W. on true line in Sec. 9.</p>
19.96	<p>To the 1/32 Sec. corner.</p> <p>Land, rich bottom, Grain and vegetables. Some dense thorn thickets.</p>
Section 11.	
<p>From the $\frac{1}{4}$ Sec. corner in the centre of Sec. 11, which is a post 3 ins. square, marked $\frac{1}{4}$ S on N face, from which</p> <p style="padding-left: 40px;">A balm 12 ins. diam. bears S. 40° W., 77 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">A cherry 4 ins. diam. bears N. 45° E. 18 lks. dist., marked $\frac{1}{4}$ S B T.,</p> <p style="text-align: center;">I run</p> <p>North on true line in Sec. 11.</p> <p style="text-align: right;">Variation 20° 15' East</p>	