

Allotments, T. 2 N., R. 33 E.

Chains	<p>over it. Pits impracticable.</p> <p>35.90 R.R., course N. 85° W.</p> <p>38.00 Fence, course N & S.</p> <p>39.80 To the 1/32 Sec. corner, 10 chains N of 1/4 Sec. corner between Secs. 10 & 11.</p> <p>Land, river bottom. Soil, 1st rate, gravelly. Grain, grass and some brush.</p>
	Section 12.
	<p>From the corner to Secs. 1, 6, 7 & 12 on East boundary of Township, which is a basalt stone 12x8x7 ins., 8 ins. in the ground, marked with 5 notches on S and 1 notch on N. edges, pits 18x18x12 ins. in each sec. 5 1/2 ft. dist. and mound of earth 2 ft. high, 4 1/2 ft. base over it. I run, South on true line between Secs. 7 & 12. Var. 19° 30' East.</p>
10.00	<p>Set basalt stone 9x8x7 ins., 6 ins. in the ground for 1/32 Sec. cor. marked 1/32 on W. face; dug pits 18x18x12 ins. N & S of stone 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p> <p>Land, rolling. Soil, ashy and barren.</p>
	<p>From the 1/4 Sec. cor. between Secs. 1 & 12, which is a charred stake with pits 18x18x12 ins. E & W of stake 5 1/2 ft. dist. and mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it. In E. pit a stake 2 ins. square, firmly set in the ground, marked 1/4 S on N. face. I run, South on true line in Sec. 12. Var. 20° East.</p>
9.00	<p>Descend bank about 30 ft.</p>
10.00	<p>Set basalt stone 10x8x7 ins. 6 ins. in the ground for 1/32 Sec. cor., marked 1/32 on W face, and raised a mound of stone over it. Pits impracticable.</p> <p>Land, rolling. Soil, 1st rate. Good grass.</p>
	<p>From 1/32 Sec. corner 10 chains South of 1/4 Sec. corner</p>