

Allotments, T. 2 N. R. 33 E.

Chains		
	<p>between Secs. 1 and 12, I run</p> <p>N. 89° 51' East on random line in Section 12.</p> <p style="text-align: center;">Variation 20° East.</p> <p>Setting temporary corner at 20 chains and at</p>	
40.00	<p>Intersect the N & S line at 1/32 Sec. corner, 10 chains</p> <p>S. of corner to Secs. 1, 6, 7 & 12.</p> <p style="text-align: center;">Thence, I run</p> <p>S. 89° 51' W. on true line in Sec. 12.</p> <p style="text-align: center;">Var. 19° 30' East.</p>	
20.00	<p>Set post 3 ft. long, 3 ins. sq. with marked stone 12 ins.</p> <p>in the ground for 1/32 Sec. corner, marked 1/32 S. on</p> <p>N. face; dug pits 18 x 18 x 12 ins., E & W of post, 5½</p> <p>ft. distant and raised a mound of earth 1½ ft. high,</p> <p>3½ ft. base over it.</p>	
33.00	Gulch, course S.	-50
38.00	Descend bank.	-30
40.00	<p>To 1/32 Sec. corner, 10 chains S. of 1/4 Sec. corner,</p> <p>between Secs. 1 & 12.</p> <p>Land, mostly level.</p> <p>Soil, 1st rate. Cultivated.</p> <hr/> <p>From the 1/16 Sec. corner, 20 chains N. of the corner to</p> <p>Secs. 7, 12, 13 & 18 which is a charred stake with pits</p> <p>18 x 18 x 12 ins. N & S of stake, 5½ ft. dist. and</p> <p>mound of earth 1½ ft. high, 3½ ft. base over it. In</p> <p>N. pit stake 2 ins. square, firmly set in the ground,</p> <p>marked 1/16 S. on W. face.</p> <p style="text-align: center;">I run,</p> <p>North on true line between Sections 7 and 12.</p> <p style="text-align: center;">Variation 19° 15' East.</p>	
2.50	Fence, course E & W.	
8.00	Road, course S.W.	
10.00	<p>Deposited a marked stone 12 ins. in the ground for 1/32</p> <p>Sec. corner; dug pits, 18 x 18 x 12 ins. N & S of cor.,</p> <p>5½ ft. distant and raised mound of earth 1½ ft. high,</p>	