

Allotments, T. 2 N. R. 33 E.

Chains	
	<p>3½ ft. base over it. In N. pit drove a stake 2 ins. sq. 2 ft. long, 12 ins. in the ground, marked 1/32 S. on W. face.</p> <p>Land, along bluff.</p> <p>Soil, 1st rate. Growing grain.</p>
	<p>From the 1/16 Sec. corner, 20 chains North of corner to Secs. 11, 12, 13 and 14, which is a charred stake 12 ins. in the ground, with pits 18 x 18 x 12 ins. in each sec. 5½ ft. distant and mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit, stake 2 ins. square, firmly in ground marked 1/16 S. on W. face.</p> <p>I run,</p>
10.00	<p>North between Secs. 11 & 12.</p> <p>Variation 21° East.</p> <p>Set basalt stone 14 x 9 x 7 ins., 9 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face; dug pits 18 x 18 x 12 ins. N & S of stone 5½ ft. distant, and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land, nearly level.</p> <p>Soil, 2d rate.</p> <p>Thorn thicket most of this line.</p>
79.80	<p>From the 1/32 Sec. corner, 30 chains N. of the corner to Secs. 11 & 12, 13 and 14.</p> <p>I run</p> <p>S. 89° 57' E. on random line in Sec. 12.</p> <p>Variation 21° East.</p> <p>Setting temporary corner at 20, 40 & 60 chains and at</p> <p>Intersect the N & S line at 1/32 Sec. corner 10 chains North of corner to Secs. 7, 12, 13 and 18 on East boundary of Tp.</p> <p>Thence, I run</p> <p>N. 89° 57' W. on true line in Sec. 12.</p>