

Chains	
	<p>S. on W. face.</p> <p style="text-align: center;">Thence, I run</p> <p>East at 19.97, found earth mound with pits 18 x 18 x 12 ins. E &amp; W of corner, 5½ ft. distant; in E. pit a stake 2 ins. square marked 1/16 S. on N. face.</p> <p style="text-align: center;">Thence</p> <p>South 20.00 chains, found pits 18 x 18 x 12 ins. E. &amp; W. of a mound of earth, 5½ ft. distant from corner. In E. pit, a stake 2 ins. square firmly set in ground, marked 1/16 S. on N. face.</p> <p style="text-align: center;">Thence</p> <p>East 20 chains, found 1/4 Sec. corner at center of section, also pits 18 x 18 x 12 ins. and in E. pit a stake marked 1/4 on N. face and at 19.90 chains further East, I found 1/16 Sec. corner. I deemed said examination sufficient to determine the fact that the N½ of Sec. 25 had been allotted into 40 acre tracts and all corners set as specified in former return of surveys. From the 1/4 Sec. corner, between Secs. 25 &amp; 30 on East boundary of Tp., which is a basalt stone 10 x 9 x 7 ins., 6 ins. in the ground marked 1/4 on W. face, pits 18 x 18 x 12 ins. N &amp; S of corner, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p style="text-align: center;">I run</p> <p>North on true line between Ranges 33 and 34 East.</p> <p style="text-align: center;">Variation 20° East.</p>
10.00	<p>Set stone 10 x 9 x 7 ins., 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face; dug pits 18 x 18 x 12 ins. N &amp; S of stone 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land, rolling.</p> <p>Soil, 1st rate and grass.</p> <p>From the 1/16 Sec. corner, 20 chains West of 1/4 Sec. corner between Secs. 25 &amp; 30 in E. boundary of Tp., which is a charred stake, 12 ins. in ground; pits</p>