

## Allotments, T. 2 N.R. 33 E.

Chains	
	<p>18 x 18 x 12 ins. E. &amp; W. of corner, 5½ ft. distant and mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, stake 2 ins. square, marked 1/16 S. on N. face.</p> <p>I run, North on true line in Sec. 25.</p> <p style="text-align: right;">Var. 20° East.</p>
10.00	<p>Set stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face; dug pits 18 x 18 x 12 ins. N &amp; S of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land, rolling. Soil, 1st rate. Good grass.</p> <p>From the 1/32 Sec. corner, 20 chains W. and 10 chains N. of 1/4 Sec. corner, between Secs. 25 &amp; 30 on E. boundary of Township,</p> <p style="text-align: center;">Thence, I run East on random line in Sec. 25.</p> <p style="text-align: right;">Variation 20° East.</p>
19.90	<p>Intersect 10 lks. North of 1/32 Sec. corner on E. bdy. of Township.</p> <p style="text-align: center;">Thence, I run N. 89° 43' W. on true line in Sec. 25.</p>
19.90	<p>To 1/32 Sec. corner.</p> <p>Land, rolling. Soil, 1st rate. Good grass.</p> <p>From the ¼ Sec. corner in the center of Sec. 25, which is a charred stake, 12 ins. in the ground, with pits 18 x 18 x 12 ins. E &amp; W. of corner, 5½ ft. distant and mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit a stake 2 ins. square marked 1/16 S. on N. face.</p> <p style="text-align: center;">Thence, I run South on true line in Sec. 25.</p> <p style="text-align: right;">Variation 19° East.</p>
20.00	<p>Set stone 10 x 8 x 7 ins., 6 ins. in the ground for 1/16 Sec. corner, marked 1/16 on W. face near the Pendleton &amp;</p>