

Allotments, T. 2 N. R. 33 E.

Chains	
	<p>LaGrande Wagon Road; dug pits 18 x 18 x 12 ins. N & S. of stone 5½ ft. dist. and raised a mound of earth 1½ ft high, 3½ ft. base over it.</p> <p>Line up mountain near Pendleton and LaGrande Wagon Road. Soil, 1st rate. Grass good.</p> <p>From the 1/16 Sec. corner, 20 chains S. of ¼ Sec. corner, between Secs. 25 & 26, which is a charred stake 12 ins. in the ground and pits 18 x 18 x 12 ins. N & S. of corner 5½ ft. dist. and mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit a stake 2 ins. square, marked 1/16 S. on W. face.</p> <p style="text-align: center;">I run,</p> <p>East on random line in Sec. 25.</p> <p style="text-align: right;">Variation 19° East.</p> <p>Setting temporary corners at 10, 20 and 30 chains and at</p>
39.95	<p>Intersect the N & S line at the 1/16 Sec. corner 20 chs. S. of ¼ Sec. corner in center of Sec. 25.</p> <p style="text-align: center;">Thence, I run</p> <p>West on true line in Sec. 25.</p> <p style="text-align: right;">Variation 19° East.</p>
9.99	<p>Set stone 10 x 8 x 7 ins. 6 ins. in the ground for 1/64 Sec. corner, marked 1/64 on N. face, and raised a mound of stone over it. Pits impracticable.</p>
19.98	<p>Set stone 11 x 8 x 7 ins. 8 ins. in the ground for 1/64 and 1/16 Section corner, marked 1/16 on N. and 1/64 on the S. face; dug pits 18 x 18 x 12 ins. E & W. of stone, 5½ ft. distant and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
29.97	<p>Set stone 12 x 10 x 5 ins., 8 ins. in the ground for 1/64 Sec. corner, marked 1/64 on N. face; dug pits 18 x 18 x 12 ins. E & W of stone, 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. over it.</p>
39.95	<p>To the 1/16 Sec. corner on West bdy.</p> <p>Land, rolling. N.W. face of Mt. Soil, 1st rate & rocky. Good grass.</p>