

Allotments, T. 2 N. R. 33 E.

Chains	
10.00	<p>From the $\frac{1}{4}$ Sec. corner, 20 chs. E. of the $\frac{1}{2}$ Sec. corner between Secs. 25 & 26, which is a charred stake 12 ins. in the ground with pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. distant, mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In E. pit a stake 2 ins. square, firmly set in the ground, marked $\frac{1}{16}$ S. on N. face.</p> <p>I run,</p> <p>South on true line in Sec. 25.</p> <p>Variation 19° East.</p> <p>Set stone 10 x 9 x 7 ins., 6 ins. in the ground for $\frac{1}{64}$ & $\frac{1}{32}$ Sec. corner, marked $\frac{1}{32}$ on S. face and $\frac{1}{64}$ on N. face. Dug pits 18 x 18 x 12 ins. N & S of stone, $5\frac{1}{2}$ ft. distant, raised a mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Line over a hill.</p> <p>Soil, rocky. Some grass.</p>
10.00	<p>From the $\frac{1}{4}$ Sec. corner between Secs. 25 & 26, which is a charred stake 12 ins. in the ground with pits 18x18x12 ins., N & S of stake $5\frac{1}{2}$ ft. distant and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In N. pit a stake 2 ins. square firmly set in the ground marked $\frac{1}{4}$ S. on W. face.</p> <p>I run</p> <p>South on true line between Secs. 25 & 26.</p> <p>Variation 19° East.</p> <p>Set stone 12 x 7 x 6 ins. 8 ins. in the ground for $\frac{1}{64}$ Sec. corner, marked $\frac{1}{64}$ on W. face, dug pits 18x18x12 ins. N & S of stone $5\frac{1}{2}$ ft. distant and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Line over hill.</p> <p>Soil, mostly rocky. Some grass.</p> <p>From $\frac{1}{64}$ Sec. corner; 20 chs. E. & 10 chs. S. of $\frac{1}{4}$ Sec. corner between Secs. 25 & 26.</p> <p>I run</p>