

Field Notes of Exterior Lines of
 Tp. 2 N. R. 33 E., by Jas. P. Currin &
 Jas. E. Noland, under Special Contract,
 Dated May 4, 1887.

	Beginning at corner to Tps. 1 & 2 N. Rs. 33 & 34 E., I run North on true line between Tps. 2 N. Rs. 33 & 34 East.	
	Thence	
	North on E. boundary Sec. 36.	
	Variation 20° East.	
7.70	Canyon, course W.	-100
26.50	Pendleton & LaGrande wagon road, West.	+200
40.00	Set a basalt stone 16 x 10 x 10 ins., 11 ins. in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face. Raised mound of stone over it. Pits impracticable.	
62.25	Canyon, course N.W.	-250
80.00	Set a basalt stone 20 x 16 x 6 ins., 15 inches in the ground for corner to secs. 25, 30, 31 & 36, marked 1 notch on S. and 5 notches on N. edges. Raised a mound of stone over it. Pits impracticable.	
	Land, mountainous, 80.00 chains.	
	Soil, 3rd rate. No timber. Good bunch grass.	
	North on E. boundary of Section 25.	
	Variation 21° 45' East.	
30.00	Top of ridge.	+200
40.00	Set a basalt stone 10 x 9 x 7 ins., 6 ins. in ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face. Dug pits 18 x 18 x 12 ins. N & S of corner, $5\frac{1}{2}$ ft. distant, raised earth mound $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.	
60.00	Deposited a charred stake 12 ins. in ground for $\frac{1}{16}$ Sec. corner. Dug pits 18 x 18 x 12 ins. N & S of corner, $5\frac{1}{2}$ ft. distant, raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over corner. In N. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ on W. face.	
80.00	Set a basalt stone 12 x 10 x 8 ins., 8 ins. in ground for corner to Secs. 19, 24, 25 & 30, marked 2 notches on S. and 4 notches on N. edges. Dug pits, 18 x 18 x 12 ins. in each Section, $5\frac{1}{2}$ ft. distant; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside.	-300