

T. 2 N. R. 33 E.

Chains	
	corner; dug pits 18 x 18 x 12 ins. N & S of corner, 5½ ft. distant; raised mound 1½ ft. high, 3½ ft. base over corner; in N. pit, drove stake 24 x 2 x 2 ins., 12 ins. in ground, marked 1/16 S. on W. face.
31.00	Road, course E & W.
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in ground for ¼ Sec. corner, marked ¼ on W. face; dug pits 18x18x12 ins., N & S of corner 5½ ft. distant; raised earth mound 1½ ft. high, 3½ ft. base alongside.
60.00	Deposited charred stake 12 ins. in ground for 1/16 Sec. corner; dug pits 18 x 18 x 12 ins. N & S of corner, 5½ ft. distant; raised a mound of earth 1½ ft. high, 3½ ft. base over corner. In N. pit, drove stake 24x2x2 ins., 12 ins. in ground. Marked 1/16 S. on W. face.
79.50	Set a basalt stone 12 x 9 x 8 ins., 8 ins. in ground for corner to secs. 7, 12, 13 & 18, marked 4 notches on S., 2 notches on N. edges; dug pits 18 x 18 x 12 ins. in each section, 5½ ft. distant; raised earth mound 2 ft. high, 4½ ft. base alongside.
	Land, rolling.
	Soil, 1st rate.
	Short grass.
<hr/>	
	North on E. boundary of Sec. 12
	Variation 20° 45' East.
20.00	Deposited a charred stake 12 ins. in ground for 1/16 Sec. corner; dug pits 18 x 18 x 12 ins. N & S. of corner, 5½ ft. distant, raised mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit, drove a stake 24 x 2 x 2 ins., 12 ins. in ground, marked 1/16 S. on W. face.
22.25	Fence, course N & S.
27.75	Road, course S.W.
30.00	O.S.L.R.R., course E & W.
40.00	Set a post 36 x 3 x 3 ins., 12 ins. in ground for ¼ Sec. corner, marked ¼ S. on W. face. Dug pits 18 x 18 x 12