

T. 2 N.R. 33 E.

Chains	
	ins. N & S of corner, $5\frac{1}{2}$ ft. dist., raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.
48.50	Umatilla River 75 lks. wide. Course, W.
60.00	Set a basalt stone 12 x 8 x 6 ins., 8 ins. in ground for 1/16 Sec. corner, marked 1/16 on W. face, from which A. Balm 20. ins. diam. bears N.35°W. 15 lks. dist. No other tree in limits, raised stone mound alongside.
65.00	Spring branch, 30 lks. wide, course W. Ascend bluff.
80.00	Set a basalt stone 12 x 8 x 7 ins., 8 inches in the ground for corner to secs. 1, 6, 7 & 12; marked 5 notches on S. and 1 notch on N. edges. Dug pits 18x18x12 ins. in each section, $5\frac{1}{2}$ ft. dist., raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside. Land, rolling. Prairie and bottom land. Prairie soil, 1st rate; soil in bottom, gravelly, 3rd rate. Thick underbrush and cottonwood timber in river bottom 50 chains.
	North on random on E. boundary Sec. 1. Variation 19° 15' East.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
76.25	Intersect N. boundary 35 lks. W. of corner to Ts. 2 & 3, N. Rs. 33 & 34 E. Thence, I run S. 16' W. on true line.
16.25	Deposited a charred stake 12 ins. in ground for 1/16 Sec. corner; dug pits 18 x 18 x 12 ins.. N & S of corner dist. $5\frac{1}{2}$ ft, raised earth mound $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In N. pit, drove stake 24 x 2 x 2 ins., 12 ins. in ground, marked 1/16 S. on W. face.
36.25	Deposited charred stake 12 ins. in ground for 1/4 Sec. corner; dug pits 18 x 18 x 12 ins.. N & S of corner, $5\frac{1}{2}$ ft. distant, raised earth mound $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In N. pit, drove a stake 24 x 2 x 2 ins. 12

†400