

T. 3 N.R. 33 E.

So. Boundary

Chains	
	<p>S. 89° 46' E. between Secs. 2 &amp; 35.</p> <p style="text-align: right;">Variation 21° East</p>
40.00	<p>Deposited a charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of corner, 5<math>\frac{1}{2}</math> ft. distant and raised a mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{4}</math> S. on N. face.</p>
80.00	<p>Set a post 48 x 4 x 4 ins., 12 ins. in the ground for corner to Secs. 1, 2, 35 &amp; 36, marked T.3 N. S. 36 on N.E., T.2 N.S.1 on S.E., R. 33 E.S.2 on S.W., S.35 on N.W., with 1 notch on E. and 5 notches on W. edges. Dug pits 18 x 18 x 12 ins. in each sec. 5<math>\frac{1}{2}</math> ft. dist., raised mound of earth 2 ft. high, 4<math>\frac{1}{2}</math> ft. base around post.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate. Poor grass.</p>
	<p>South 89° 46' E. between Secs. 1 &amp; 36.</p> <p style="text-align: right;">Variation 20° 45' East.</p>
5.50	Gulch, course N.W.
20.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of corner 5<math>\frac{1}{2}</math> ft. distant and raised a mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>
36.40	Road, course NE & SW.
40.00	<p>Deposited a charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of corner 5<math>\frac{1}{2}</math> ft. distant and raised a mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked <math>\frac{1}{4}</math> S. on N. face.</p>
60.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 Sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of corner</p>

-100