

T. 2 N., R. 33 E.

Chains	
	5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on N face.
80.00	To corner to Ts. 2 & 3, N. Rs. 33 & 34 E. Land, rolling and broken. Soil, 2nd rate. No timber.
North Boundary T. 1, N., R. 33 E. (S. boundary T. 2 N.R.33 E.)	
	At corner to Tps. 1 & 2 N., R. 32 & 33 E. Thence, I run N. 89° 57' E. on N. boundary of Section 6.
16.95	Variation 20° East.
19.65	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor.; dug pits 18x18x12 ins. E & W of cor. 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove stake 2 ft. long, 2 ins. square 12 ins. in ground marked 1/16 S on N face.
23.90	Wagon Road, course N.W.
31.85	Trail, " " "
36.95	Deposited a charred stake 12 ins. in the ground for ¼ Sec. cor. Dug pits 18x18x12 ins. E & W of cor. 5½ ft. dist. Raised earth mound 1½ ft. high, 3½ ft. base over it; in E. pit drove a stake 2 ft. long 2 ins. square marked ¼ S. on N. face - 12 ins. in the ground.
50.95	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor.; dug pits 18x18x12 ins. E & W of cor. 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on W. face.
66.50	Wagon course N & S.
76.95	Set a basalt stone 12x8x6 ins., 8 ins. in the ground for cor. to secs. 5, 6, 31 and 32. Marked 5 notches on E and 1 on W edges. Dug pits 18x18x12 ins. each sec. 5½ ft. dist. and raised earth mound 2 ft. high, 4½ ft. base alongside.