

S. boundary Tp. 1 N., R. 33 East
(N. bdy. T. 1 N., R. 33 E.)

Chains		
	mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it.	
60.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on W face.	
65.00	Gulch, West.	-200
75.00	Top of ridge W.	+200
80.00	Set basalt stone 10 x 10 x 10 ins., 6 ins. in the ground for cor. to secs. 25, 26, 35 and 36, marked with 1 notch on S and E. edges; dug pits 18 x 18 x 12 ins. in each sec. $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high $4\frac{1}{2}$ ft. base over it.	
	Land, mountainous 80.00 chains.	
	Soil, 2nd rate; some rock.	
	Grass, fair.	
<hr/>		
	East on random between secs. 25 and 36.	
	Var. 20° East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner and at	
79.50	Intersect E. bdy. of Township at cor. to secs. 25, 36, 30 and 31.	
	Thence	
	West on true line.	
	Var. $21^{\circ}45'$ East.	
	Descend.	
12.25	Dry branch N.	-300
12.50	Begin ascent.	
31.00	Pendleton and La Grande wagon road. N.W.	
36.00	Summit ridge North.	+500
39.75	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x 12 ins. E & W of stone $5\frac{1}{2}$ ft. distant; raised mound of stone and earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it.	