

Allotments, T. 2 N., R. 33 E.

Chains	line. Some brush in river bottom.
	North on random between secs. 1 & 2.
	Var. $20\frac{1}{4}^{\circ}$ East.
76.25	Set temporary cors. at 20, 40 and 60 chains and at Intersect N. bdy of Township 30 lks. W. of cor. to secs. 35, 36, 1 and 2.
	Thence
16.25	S. 13' W. on true line. Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.
35.50	Wagon road, S.W.
36.25	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins, N & S of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
56.25	Set charred stake 12 ins. in the ground for 1/16 sec.cor; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S.on W. face.
66.15	Stream 20 lks., runs West.
76.25	Cor. to secs. 1, 2, 11 and 12.
	Land, rolling.
	Soil, 2nd rate.
	Thickly set with rabbit brush. Mostly adapted to cultivation.
	Little bunch grass.