

Subdivisions, T. 2 N., R. 33 E.

Chains		
	North between Secs. 34 & 35. Variation 21° East.	
6.50	Draw W.	-20
11.10	Wagon Road, E & W.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor.; dug pits 18x18x12 ins. N and S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S on W. face.	
29.70	Enter field S.W.	
40.00	Set basalt stone 12x10x6 ins., 8 ins. in the ground for ¼ Sec. cor., marked ¼ on W. face; dug pits 18x18x12 ins. N and S of cor. 5½ ft. dist, and raised mound of earth 1½ ft. high, 3½ ft. base over it.	
44.10	Fence and leave field S.W.	
53.50	Trail W.	
55.00	Dry ditch N.W.	-10
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. N and S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.	
80.00	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for cor. to secs. 26, 27, 34 and 35 marked with 1 notch on S and 2 notches on E edges and raised mound of stone over it Land, level. Soil, 1st rate. Some bunch grass but closely eaten off.	
	East on random between secs. 26 & 35. Variation 20° East. Set temporary cors. at 20, 40 and 60 chains and at 79.80 Intersect N & S line at cor. to secs. 25, 26, 35 and 36. Thence West on true line. Variation same.	