

## Subdivisions, T. 2 N., R. 33 E.

Chains	
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E & W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
68.50	Wagon road.
79.80	Cor. to secs. 22, 23, 26 & 27. Land, level. Soil, 1st rate. Well adapted to agriculture. Small rabbit brush. Grass short.
North between secs. 22 and 23.	
Variation 20° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. N & S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W face.
39.25	Dry ditch W.
40.00	Set basalt stone 16x12x18 ins. 12 ins. in the ground for ¼ sec. cor. marked ¼ on W. face; dug pits 18x18x12 ins. N & S of stone 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.
47.50	Wagon road E & W.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. N & S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
80.00	Deposited charred stake 12 ins. in the ground for cor. to secs. 14, 15, 22 and 23.; dug pits 18x18x12 ins. in each sec., 5½ ft. dist; raised mound of earth 1½ ft. high, 3½ ft. base over it and in S.E. pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground marked T2N S14 on N.E., R33E. S23 on S.E., S22 on S.W., S15 on NW faces with 3 notches on south and 2 notches on E. edges. Land, level. Soil, 1st rate. Grass short.