

## Subdivisions, T. 2 N., R. 33 E.

Chains	
	East on random between secs. 14 and 23. Variation 20° East.
80.00	Set temporary cors. at 20, 40 and 60 chains and at Intersect N & S line at cor. to secs. 13, 14, 23 and 24. Thence, West on true line. Variation same.
20.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. cor. marked 1/16 S on N face; dug pits 18x18x12 ins. E & W of post 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.
23.00	Wagon road N.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S. on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E and W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
80.00	Cor. to secs. 14, 15 22 and 23. Land, level. Soil, 1st rate. Grass short.
	North between secs. 14 and 15. Var. 20° East
6.40	Wagon road N.W.
10.00	Same N.E.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. N and S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W face.