

Subdivisions, T. 2 N., R. 33 E.

Chains	
	square, 12 ins. in the ground, marked 1/16 S on N. face.
40.10	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake $5\frac{1}{2}$ ft. dist.; raised mound of stone and earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/4 S on N face.
60.15	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
75.00	Wagon road N.E.
80.20	Corner to secs. 15, 16, 21 and 22. Land, level. Soil, 1st rate. All good agricultural land.
	North between secs. 15 and 16. Variation $20\frac{1}{4}^{\circ}$ East.
20.00	Drove charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W face.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.