

## Subdivisions, T. 2 N., R. 33 E.

Chains	
73.80	Wagon road W.
78.80	Spring branch N.W.
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for corner to secs. 9, 10, 15 and 16, marked T2 N S10 on N.E., R33E S15 on S.E. , S16 on S.W. and S9 on N.W. faces, with 4 notches on S and 3 notches on E. edges; dug pits 18 x 18 x 12 ins. in each sec., 5½ ft. dist.; raised mound of earth 2 ft. high, 4½ ft. base around it.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>All good farming land.</p>
	East on random between secs. 10 and 15.
	Variation 20½° East.
	Set temporary corners at 20, 40 and 60 chains and at
79.80	Intersect N & S line 20 lks. N of corner to secs. 10, 11, 14 and 15.
	Thence
	N 89° 51' W on true line.
	Var. 20-3/4° East.
19.95	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 on N face.</p>
39.90	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N face.</p>
42.75	Gulch North.
59.85	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins E &amp; W of stake, 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base</p>