

Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>marked R33E S10 B.T.</p> <p>A balm 12 ins. diam. bears N.40°W 112 lks. dist.</p> <p>marked T2 NR33 E S4 B.T.</p> <p>No other tree in limits, raised mound of stone over corner.</p> <p>Land, mostly bottom.</p> <p>Soil, 2nd rate. Some gravel.</p> <p>Heavy Cottonwood and underbrush 48 chs.</p>
	<hr/> <p>East on random between secs. 3 and 10.</p> <p style="text-align: right;">Var. 20½° East.</p> <p>Set temporary corners at 20, 40 and 60 chains and at</p>
79.90	<p>Intersect N & S line at cor. to secs. 2, 3, 10 and 11.</p> <p style="text-align: center;">Thence</p> <p>West on true line.</p> <p style="text-align: right;">Variation 20° East.</p>
	<p>Through dense brush.</p>
28.00	<p>Umatilla river bed N.E. 100 lks.</p>
39.95	<p>Set boulder stone 14 x 8 x 6 ins., 10 ins. in the ground for ¼ sec. corner, marked ¼ on N. face, from which</p> <p>A balm 26 ins. diam. bears S37½° W. 332 lks. dist., marked ¼ S.B.T.</p> <p>No other trees in limits, raised mound of stone 1½ ft. high, 3½ ft. base around corner.</p>
68.00	<p>Umatilla river S.E. by E.</p>
79.90	<p>Cor. to secs. 3, 4, 9 and 10.</p> <p>Land, bottom; soil, 2nd and 3rd rate.</p> <p>Heavy timber: Balm, cherry and pine 79.90</p>
	<hr/> <p>North on random between secs. 3 and 4.</p> <p style="text-align: right;">Variation 20½° East.</p> <p>Set temporary corners at 20, 40 and 60 chains and at</p>
75.70	<p>Intersect N. boundary Township 20 links E. of corner to secs. 3, 4, 33 and 34.</p> <p style="text-align: center;">Thence</p>