

Subdivisions, T. 2 N., R. 33 E.

Chains	
26.00	Draw N.E.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on W face.
60.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake, $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S on W. face.
80.00	Deposited charred stake 12 ins. in the ground for corner to secs. 28, 29, 32 and 33. Dug pits 18 x 18 x 12 ins. in each sec., $5\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it and in S.E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T2N S28 on N.E.; R33E S33 on S.E.; S32 on S.W. and S29 on N.W. faces, with 1 notch on S and 4 notches on E. edges.
	Land, level.
	Considerable rabbit brush.
	Soil, a kind of ashy, white sandy nature; 3rd rate. Some alkali.
	<hr/> East on random between secs. 28 and 33.
	Variation 21° East.
	Set temporary corners at 20, 40 and 60 chains and at
80.00	Intersect N and S line 20 lks. N of cor. to secs. 27, 28, 33 and 34.
	Thence