

## Subdivisions, T. 2 N., R. 33 E.

Chains		
32.00	Dry ditch N.W.	
32.75	Wagon road N.W.	
40.00	Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked ¼ S on W. face.	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W. face.	
65.75	Spring branch 3 lks.	-10
78.00	Fence and leave field. Ascend gradual slope.	
80.00	Set post 4 ft. long, 4 ins. square 24 ins. in the ground for cor. to secs. 20, 21, 28 and 29, marked T2N S21 on N.E.; R33E S28 on S.E.; S29 on S.W. and S20 on N.W. faces with 2 notches on S. and 4 notches on E. edges; dug pits 18 x 18 x 12 ins. in each sec. 5½ ft. dist; raised mound of earth 2 ft. high, 4½ ft. base around post. Land, level. Soil, 1st rate. Good agricultural land.	
	East on random between secs. 21 and 28. Variation 20° East.	
	Set temporary corners at 20, 40 and 60 chains and at	
80.00	Intersect N & S line at corner to secs. 21, 22, 27 and 28. Thence	
	West on true line. Variation 19°15' East.	
3.00	Wagon road N.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. and dug pits 18 x 18 x 12 ins. E and W of stake 5½	