

## Subdivisions, T. 2 N., R. 33 E.

Chains	square, 12 ins. in the ground marked $\frac{1}{4}$ S. on W. face.	
50.00	Tudie Willows Creek 5 lks. W. Ascend.	
60.00	Top of hill and deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in North pit drove post 2 ft. long, 2 ins. square 12 ins. in the ground, marked $\frac{1}{16}$ S on W face.	+100
80.00	Deposited charred stake 12 ins. in the ground for corner to secs. 16, 17, 20 and 21; dug pits 18 x 18 x 12 ins. in each sec. $5\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it and in S.E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked T2N S16 on N.E.; R33E S21 on S.E.; S20 on S.W. and S17 on N.W. faces with 3 notches on S and 4 notches on E. edges. Land, rolling. Soil, 1st rate on high rolling land, but poor on lower land.	
	East on random between secs. 16 and 21. Variation $21^{\circ}$ East. Set temporary cors. at 20, 40 and 60 chains and at Intersect N & S line 45 lks. N of corner to secs. 15, 16, 21 and 22. Thence N. $89^{\circ} 41'$ W. on true line. Variation $20\frac{1}{4}^{\circ}$ East.	
79.60		
19.90	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. corner. Dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.	