

## Subdivisions, T. 2 N., R. 33 E.

Chains	ins. square 12 ins. in the ground marked 1/16 S on W. face.
68.00	Old Emigrant road N.W. Descend gradually.
80.00	Set post 4 ft. long, 4 ins. square 24 ins. in the ground for corner to secs. 8, 9, 16 and 17, marked T2N S9 on NE; R33E S16 on S.E.; S17 on S.W. and S8 on N.W. faces with 4 notches on S and E. edges; dug pits 18 x 18 x 12 ins. in each sec., 5½ ft. distant; raised mound of earth 2 ft. high, 4½ ft. base around corner. Land, level or nearly so. Soil, 1st rate. Some bunch grass.
	East on random between secs. 9 and 16. Variation 21° East. Set temporary corners at 20, 40 and 60 chains and at
80.00	Intersect N & S line 70 links N. of corner to secs. 9, 10, 15 and 16. Thence N. 89° 30' W. on true line. Variation 20½° East
2.25	Dry ditch N.W.
3.50	Wagon road N.W.
6.50	Wagon road N.W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E and W. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼S on N. face.